

2013 QBS
Request for Statement of Interest (SOI)
TANNER ROAD OVER LAKE RUN CREEK
BRIDGE REPLACEMENT IMPROVEMENT
Section Number 11-00163-01-BR

The Kane County Division of Transportation is in need of professional services from a qualified engineering firm to provide Phase III Construction Observation Engineering Services for the New Construction project, as above referenced.

The attached *Preliminary Scope of Services and Pre Final Construction Plan and Specifications* provide a summary of major items that will be encountered during the course of the construction observation services required.

At this time the County anticipates starting this work in early to mid-2013 with approximately 4-5 months to complete the work.

The Statement of Interest shall be submitted electronically via **KDOT QBS** no later than 2:00 pm on November 21, 2013 and should be addressed to David Boesch, Chief of Construction.

If you plan to enter into a joint venture with another firm for this project please note this on your Statement of Interest, including the name of the firm you are entering into a joint venture with for this project.

Short-listed firms will be posted on our website at www.co.kane.il.us/dot. Click on the link labeled "Request for Consultant Services", then click on the link labeled "Summary Table".

Firms interested in providing services to Kane County are hereby notified of their required compliance with Kane County's Ethic Ordinance (Ordinance No. 10-206) in particular, Section 10, page 15 of Ordinance No. 10-206. The complete Ethics Ordinance is available online at: <http://www.countyofkane.org/SiteCollectionDocuments/ethics.pdf>. Firms shall provide required Ethic Ordinance information directly to the Kane County Purchasing Department at the following address:

Kane County Government Center
Purchasing Department, Bldg. A
719 S. Batavia Ave.
Geneva, IL 60134

A Statement of Interest (SOI) received after the above noted deadline will not be used as part of our consultant selection process.

Please refer to the following Description of Project Scope for more information on this project.

I. PROJECT DESCRIPTION

A. INTRODUCTION

1. The Kane County Division of Transportation (KDOT) approved the attached Preliminary set of plans for the improvement of the Tanner Road Bridge over Lake Run Creek dated March 19, 2013 and prepared by the consulting firm of Baxter and Woodman Consulting Engineers.
2. A brief outline of the project scope to assist you in your submittal is as follows:
3. The above project will replace an old single span beam bridge on spread footings with a 2 span reinforced concrete slab structure set on pile bent piers and abutments with concrete parapets, asphalt surface approaches and new guardrail. The bridge is located within a low to medium volume traffic corridor between Deerpath and Bliss Roads in Blackberry Township, unincorporated Kane County. The proposed project is estimated at a cost of approximately \$1.4 Million dollars with an anticipated duration of approximately 75 WDs. The project will be completed within one construction season with an anticipated start of spring/summer 2014. The total length of the improvement is 881 feet. The bridge replacement will be accomplished with a detour using Orchard, Randall, Main St. and Bliss Roads as run around routes. The project will be constructed under medium traffic with volumes approaching or exceeding 2000 ADTs on Tanner Road. Local businesses, residential homes and recreational facilities are located near the project corridor, and the area is at times, heavily traveled by both commercial and private trucks and automobiles traveling to the surrounding communities of North Aurora and Sugar Grove. All driveways within and impacted by the project are to remain accessible during the project for completion.
4. The improvement will involve the demolition of the existing structure and replacement with a reinforced concrete slab structure. Sections of pavement leading up to the bridge will be both surface milled and fully removed and replaced to facilitate the replacement and render a smooth riding condition once the structure has been replaced.
5. Relocations of existing utilities may be required and may involve relocations of aerial power and cable TV lines as well as relocations of underground natural gas and telephone lines as referenced in the specifications. These utilities may require ongoing coordination between the prime contractor, multiple sub-contractors and utility companies to relocate new services efficiently. The rapid and accurate relocation of these utilities is critical to the successful completion of the project within the given time parameters.
6. The project has restoration and landscaping at approximately 1.0 acre.
7. There are no Infrastructure improvements on this project.
8. The project will be handled via a closed road with a posted detour route to reduce construction time and enhance worker safety. While restrictions involving the timing and

duration of the detour are not currently specified in the Special Provisions, it is not uncommon to require organized coordination of the detour with KDOT, IDOT and the surrounding local Villages affected by the project.

9. Major construction challenges involve demolition of the old structure, complying with specified weight limits, site grading, compressed construction schedule, water diversion, and utility relocation, acquiring a staging area, pile driving and installation, maintenance of traffic, utility relocations and in stream bridge work.
10. This project will be funded with local funds with construction observation and documentation as per IDOT policies and procedures. Any additional details should be referenced in an attached preliminary plan set.